



**NOTES:**

1. COLLARS SHALL BE INSTALLED AROUND ALL VALVE BOXES AND MANHOLES WITHIN ROADWAYS. COLLARS SHALL BE CONSTRUCTED UTILIZING SP3 ASPHALT OR CONTROL DENSITY FILL.
2. THICKENED ASPHALT SHALL BE COMPACTED WITH A MECHANICAL TAMPER, WITH A MAXIMUM LIFT THICKNESS OF 3", PRIOR TO OVERLAYING WITH ASPHALT PAVEMENT.
3. COLLAR REQUIRES AN INSPECTION DURING INSTALLATION.

APPROVED BY:  
  
 CITY ENGINEER, P.E.      3/19/19      DATE:

POST FALLS STANDARDS FOR PUBLIC WORKS CONSTRUCTION

**THICKENED COLLAR**

STANDARD DRAWING  
 NO. **SD 404**